

EXHIBIT “E”

INTERIOR PRODUCT INFORMATION



963, 9631, 9632

Surface-Mounted Baby Changing Station

Model 963 – Gray and White Speckled **Bradex**®

Model 9631 – Light Grey **Bradex**®

Model 9632 – Cream **Bradex**®

Product Materials

Bacterial-resistant, high density polyethylene with steel-to-steel support hinges. Pneumatic gas shock mechanism opens and closes unit smoothly. Liner dispenser and purse/diaper bag hooks molded in. ADA compliant nylon buckle is adjustable with one hand.

STRENGTH NOTE: Unit complies with ASTM F2285 Standard that requires commercial diaper changing stations be able to support a static load of up to 250 lb.

Guide Specification

Surface-mounted baby changing station shall be gray and white speckled (963), solid light grey (9631), or cream colored (9632) molded bacterial-resistant, high density polyethylene. Steel-to-steel support hinges with pneumatic gas shock mechanism. Unit shall have integrated liner dispenser and bag hooks. Unit shall have an anti-microbial safety belt. Warning labels are printed in English, Spanish, French, and Braille. Unit shall be operable with less than 5 lb of force and complies with ASTM F2285 Standard.

Overall dimensions: 34-1/4"W x 15-3/8"H x 4"D.



Installation

Verify all rough-in dimensions prior to installation. Secure to wall through mounting holes. Mounting hardware for typical conditions is included.

WARNING: Be sure to use reinforced backing behind wall where mounting screws or anchoring devices are installed to ensure adequate support for the baby changing station. All anchoring devices must be appropriate for specific wall construction. Severe personal injury and/or property damage may result from improper mounting.

Product Compliance

Complies with

- ADA¹



¹ Product is ADA compliant when it opens with less than 5 lb of force and projects less than 4" from the wall when closed.

Service Parts Available

Part Number	Description
P15-491	Replacement Strap

☒ Consult local and national accessibility codes for proper installation guidelines.

☒ Conformity and compliance to local and national codes is the responsibility of the installer.

Orders composed of products indicated as **Bradex**® will be available to ship in three days after receipt of order at the factory. There is no pricing penalty for this service from Bradley.

Page 1 of 2

9/9/2022

[View Latest Version](#)

This information is subject to change without notice.

Bradley_BabyChanger_963_31_32

© 2022 Bradley
P.O. Box 309, Menomonee Falls, WI 53052-0309
800 BRADLEY (800 272 3539) +1 262 251 6000
bradleycorp.com




963, 9631, 9632

Surface-Mounted Baby Changing Station

Dimensions

(mm)



Orders composed of products indicated as **Bradex**® will be available to ship in three days after receipt of order at the factory. There is no pricing penalty for this service from Bradley.

Page 2 of 2

9/9/2022

[View Latest Version](#)

This information is subject to change without notice.
Bradley_BabyChanger_963_31_32

© 2022 Bradley
P.O. Box 309, Menomonee Falls, WI 53052-0309
800 BRADLEY (800 272 3539) +1 262 251 6000
bradleycorp.com

PRODUCT SPECIFICATIONS

Elkay ezH2O® Bottle Filling Station, & Bi-Level High Efficiency Vandal-Resistant Cooler, Non-Filtered Refrigerated Stainless. Chilling Capacity of 8.0 GPH (gallons per hour) of 50° F drinking water, based on 80° F inlet water and 90° F ambient, per ASHRAE 18 testing. Features shall include Antimicrobial, Green Ticker™, Hands Free, High Efficiency, Laminar Flow, Real Drain, Vandal Resistant. Furnished with Vandal Resistant StreamSaver™ bubbler. Electronic Bottle Filler Sensor with Mechanical Front Bubbler Button activation. Product shall be Wall Mount (On Wall), for Indoor applications, serving 2 station(s). Unit shall be certified to UL 399 and CAN/CSA C22.2 No. 120. Unit shall be lead-free design which is certified to NSF/ANSI 61 & 372 (lead free) and meets Federal and State low-lead requirements.

Special Features:	Antimicrobial, Green Ticker™, Hands Free, High Efficiency, Laminar Flow, Real Drain, Vandal Resistant
Finish:	Stainless Steel
Power:	115V/60Hz
Bubbler Style:	Vandal Resistant StreamSaver™
Activation by:	Electronic Bottle Filler Sensor with Mechanical Front Bubbler Button
Mounting Type:	Wall Mount (On Wall)
Chilling Capacity*:	8.0 GPH
Full Load Amps	1
Rated Watts:	260
Dimensions (L x W x H):	36-1/8" x 18-5/8" x 46-1/4"
Approx. Shipping Weight:	112 lbs.
Installation Location:	Indoor
No. of Stations Served:	2

*Based on 80° F inlet water & 90° F ambient air temp for 50° F chilled drinking water.

- Mechanically-Activated bubbler continues to supply water in event of service disruptions.
- High-performance compressor and insulation greatly reduce energy consumption.
- Green Ticker: Informs user of number of 20 oz. plastic water bottles saved from waste.
- Laminar flow provides clean fill with minimal splash.
- Silver Ion Antimicrobial protection on key plastic components to inhibit the growth of mold and mildew.
- Real Drain System eliminates standing water.

COOLING SYSTEM

- Compressor: Hermetically-sealed, reciprocating type, single phase. Sealed-in lifetime lubrication.
- Condenser: Fan cooled, copper tube with aluminum fins. Fan motor is permanently lubricated.

PART: _____ QTY: _____
 PROJECT: _____
 CONTACT: _____
 DATE: _____
 NOTES: _____
 APPROVAL: _____



AMERICAN PRIDE. A LIFETIME TRADITION. Like your family, the Elkay family has values and traditions that endure. For almost a century, Elkay has been a family-owned and operated company, providing thousands of jobs that support our families and communities.



Included with Product: Water Cooler (VRCGRNTL8WSC), Bottle Filler (EZWSR)

▼ Ships in multiple boxes.

PRODUCT COMPLIANCE

ADA & ICC A117.1
 ASME A112.19.3/CSA B45.4
 Buy American Act
 CAN/CSA C22.2 No. 120
 GreenSpec®
 NSF/ANSI 61 & 372 (lead free)
 UL 399



Complies with ADA & ICC A117.1 accessibility requirements when installed according to the requirements outlined in these standards. Installation may require additional components and/or construction features to be fully compliant. Consult the local Authority Having Jurisdiction if necessary.

[Installation Instructions \(PDF\)](#)

5 Year Limited Warranty on the refrigeration system of the unit. Electrical components and water system are warranted for 12 months from date of installation. **Warranty pertains to drinking water applications only. Non-drinking water applications are not covered under warranty.**

[Warranty \(PDF\)](#)

OPTIONAL ACCESSORIES

EW3000 - Elkay WaterSentry Plus Filter System Kit (Bottle Fillers)
98324C - Accessory - Cane Apron for HAC, HVR, EMABF & VRC Models (Stainless)

In keeping with our policy of continuing product improvement, Elkay reserves the right to change product specifications without notice. Please visit elkay.com for the most current version of Elkay product specification sheets. This specification describes an Elkay product with design, quality, and functional benefits to the user. When making a comparison of other producers' offerings, be certain these features are not overlooked.

- Cooling Unit: Combination tube-tank type. Continuous copper tubing with is fully insulated with EPS foam that meets UL requirements for self-extinguishing material.
- Refrigerant Control: Refrigerant HFC-134a is controlled by accurately calibrated capillary tube for positively trouble-free operation.
- Temperature Control: Easily accessible enclosed adjustable thermostat is factory preset. Requires no adjustment other than for altitude requirements.

In keeping with our policy of continuing product improvement, Elkay reserves the right to change product specifications without notice. Please visit elkay.com for the most current version of Elkay product specification sheets. This specification describes an Elkay product with design, quality, and functional benefits to the user. When making a comparison of other producers' offerings, be certain these features are not overlooked.


IMPORTANT! INSTALLER PLEASE NOTE :

This water cooler has been designed and built to provide water to the user which has not been altered by materials in the cooler waterways. The grounding of electrical equipment such as telephone, computer, etc. to water lines is a common procedure. The grounding may be in the building but may also occur away from the building. This grounding can cause electrical feedback into a water cooler creating an electrolysis which creates a metallic taste or causes an increase in the metal content of the water. This condition is avoidable by installing the cooler using the proper materials as shown below.



NOTICE

This water cooler must be connected to the water supply using a dielectric coupling. The cooler is furnished with a non-metallic strainer which meets this requirement. The drain trap which is provided by the installer should also be plastic to completely isolate the cooler from the building plumbing system. Bottle filler unit on bracket attached to wall by 6 holes (as shown). Water and electrical will connect through pre-punched hole in basin. These products are designed to operate on 20 psi to 105 psi supply line pressure. Simultaneous operation of both bubblers on a bi-level unit may not be possible depending on water supply pressure. If simultaneous operation is desired, please ensure a minimum of 50 psi supply.

OPERATION OF QUICK CONNECT FITTINGS



Pushing tube in before pulling it out helps to release tube



LEGEND:

A = Recommended Water Supply location. Shut-off Valve (not furnished) to accept 3/8\" O.D. unplated copper tube. Up to 3\" (76mm) maximum out from wall.

B = Recommended Waste Outlet location. To accommodate 1-1/2\" nominal drain. Drain stub 2\" (51mm) out from wall.

C = 1-1/2\" Trap (not furnished).

D = Electrical Supply (3) Wire Recessed Box Duplex Outlet.

E = Insure proper ventilation by maintaining 6\" (152mm) minimum clearance from cabinet louvers to wall.

F = 7/16\" (11mm) Bolt Holes for fastening to wall.

Note : New Installations Must Use Ground Fault Circuit Interrupter (GFCI). It is highly recommended that the circuit be dedicated and the load protection be sized for 20 amps.

REDUCE HEIGHT BY 3 INCHES FOR INSTALLATION OF CHILDRENS ADA COOLER

In keeping with our policy of continuing product improvement, Elkay reserves the right to change product specifications without notice. Please visit elkay.com for the most current version of Elkay product specification sheets. This specification describes an Elkay product with design, quality, and functional benefits to the user. When making a comparison of other producers' offerings, be certain these features are not overlooked.

Installation/Care/Use manual

Non-Refrigerated Composite VR Fountain with Back Panel



Installer

To assure you install this model easily and correctly, PLEASE READ THESE SIMPLE INSTRUCTIONS BEFORE STARTING THE INSTALLATION. CHECK YOUR INSTALLATION FOR COMPLIANCE WITH PLUMBING, ELECTRICAL AND OTHER APPLICABLE CODES. After installation, leave these instructions inside the fountain for future reference.

IMPORTANT

ALL SERVICE TO BE PERFORMED BY AN AUTHORIZED SERVICE PERSON

IMPORTANT! INSTALLER PLEASE NOTE.

THE GROUNDING OF ELECTRICAL EQUIPMENT SUCH AS TELEPHONE, COMPUTERS, ETC. TO WATER LINES IS A COMMON PROCEDURE. THIS GROUNDING MAY BE IN THE BUILDING OR MAY OCCUR AWAY FROM THE BUILDING. THIS GROUNDING CAN CAUSE ELECTRICAL FEEDBACK INTO A FOUNTAIN, CREATING AN ELECTROLYSIS WHICH CAUSES A METALLIC TASTE OR AN INCREASE IN THE METAL CONTENT OF THE WATER. THIS CONDITION IS AVOIDABLE BY USING THE PROPER MATERIALS AS INDICATED. ANY DRAIN FITTINGS PROVIDED BY THE INSTALLER SHOULD BE MADE OF PLASTIC TO ELECTRICALLY ISOLATE THE FOUNTAIN FROM THE BUILDING PLUMBING SYSTEM.




FIG. 1

OPERATION OF QUICK CONNECT FITTINGS




FIG. 2

EDFPVR217C ROUGH-IN COMPOSITE BACK PANEL

DETAIL 1

WASHER REQUIRED TO MINIMIZE
BREAKAGE OF FOUNTAIN.
ITYP. ALL 4 MOUNTING BOLTS,
MOUNTING BOLTS & WASHERS
NOT INCLUDED)






FIG. 3

LEGEND:
 A = RECOMMENDED WATER SUPPLY LOCATION 3/8" O.D. UNPLATED COPPER TUBE CONNECT
 B = RECOMMENDED LOCATION FOR WASTE OUTLET 1-1/4" O.D. DRAIN
 C = MOUNTING HOLES FOR SECURING FOUNTAIN TO WALL (BLOCKING & WALL SUPPORT IS REQUIRED IN THESE AREA FOR PROPER SUPPORT OF FOUNTAINS)
 D = 1 - 1/4" TRAP FURNISHED

EDFPVR217RC Install Instructions



Attach the back panel to the wall using the top two holes (1) and (2) in panel. Do not tighten the back panel down, allow some slack for sliding the fountain over bolts.



Slide fountain onto partial secured bolts and tighten down at (1) and (2). Do not over tighten as cracking of the fountain or backing could occur. Secure the fountain with last 2 bolts at points (3) and (4).

FIG. 4

INSTALLATION INSTRUCTIONS

MARBLYTE BACK PANEL

1. **Wall should already be framed for the fountain** using the positioning dimensions shown in Fig 3. Shown dimensions pertain to installation location (framing must support up to 150 lbs. weight).
2. **Install rough-in plumbing** as shown in Fig 3. Run supply water inlet line and connect to a service stop (not provided). Turn on supply water and flush thoroughly. Close water supply.
3. **Remove bottom access panel** from fountain basin and save the screws. Install the fountain to the back panel and wall using (4) 5/16" bolts and washers (not provided). Bolts should be long enough to securely fasten the fountain to the wall. Tighten securely, but do not over tighten. Over tightening will crack the Marblyte Fountain.
4. **Remove elbow from end of p-trap** (item 1) and attach it to drain tube. Re-attach elbow to p-trap and cut waste tube to required length using plumbing hardware and trap as guide.
5. **Make water supply connections** from service stop to the fountain strainer (Item 16) by inserting the water inlet line into the inlet side of strainer until it reaches a positive stop about 3/4", (See Fig 1, Page 1). Turn on water supply and check for leaks. Newly installed water supply line should be insulated after leak check is completed. **DO NOT SOLDER TUBES INSERTED INTO THE STRAINER AS DAMAGE TO THE O-RINGS MAY RESULT.**
6. **These products are designed** to operate on 20-105 PSI supply line pressure. If inlet pressure is above 105 PSI, a pressure regulator must be installed in the supply line. Any damage caused by reason of connecting these products to supply line pressure lower than 20 PSI or higher than 105 PSI is not covered by warranty.
7. **Check stream height from bubbler.** Stream height is factory set at 45-50 PSI. If supply pressure varies greatly from this, adjust the screw on regulator item 3 (See Fig 5) by using a small screwdriver through the small hole in the push button item 8 (See Fig 5). Clockwise adjustment will raise stream height and counter-clockwise adjustment will lower stream height. For best adjustment stream height should be approximately 1-1/2" (38mm) above the bubbler.
8. **Replace bottom access panel** to fountain basin using screws provided. Tighten securely.

Care and Maintenance of Halsey Taylor Marblyte Fountains

Elkay Composite fountains provide an extremely durable, nonporous surface which resists staining. Care is very simple. Routine cleaning with a soft sponge or cloth, or with water or non-abrasive aerosol foam cleaner, is all that is normally needed to give many years of trouble free service. Cleaners left standing on the fountain surface can dull the surface finish. Be certain to rinse all cleaning agents completely and polish with a soft cloth.

Harsh abrasive cleaners are not required and should not be used.

Mild abrasives such as liquid automotive cleaning compound or baking soda paste will remove simple scratches and stains. Cigarette burns can normally be removed without noticeable effect. Deeper scratches or gouges can be corrected with fine grit sandpaper (240 grit then 400 grit) or a green Scotchbrite pad.

To maintain or regain luster and make cleaning easier, periodic applications of automobile wax or like products will keep the finish looking like new.

TROUBLE SHOOTING & MAINTENANCE

Orifice Assy: Mineral deposits on orifice can cause water flow to spurt or not regulate. Mineral deposits may be removed from the orifice with a small round file not over 1/8" diameter or small diameter wire. **CAUTION: DO NOT** file or cut orifice material.

Stream Regulator: If orifice is free of material deposits, regulate flow as in instructions on (Page 4, Step 8). If replacement is necessary, see parts list for correct regulator part number.

Actuation of Quick Connect Water Fittings: Cooler is provided with lead-free connectors which utilize an o-ring water seal. To remove tubing from the fitting, relieve water pressure, push in on the gray collar while pulling on the tubing. (See Fig 2, Page 1). To insert tubing, push tube straight into fitting until it reaches a positive stop, approximately 3/4".





FIG. 5

TOP VIEW
FIG. 6

PARTS LIST		
ITEM NO.	PART NO.	DESCRIPTION
1	LK464	Drain
2	75534C	Screw - #10-24 Pinned Torx
3	98731C	Kit - Regulator/Holder/Nuts
4	27658C	Bottom - Plate (HRFG-E)
	27201C	Bottom - Plate (HRFG-S)
5	45336C	Kit - Drain Strainer/Ferrule
6	56092C	Poly Tubing (Cut To Length)
7	75554C	Insert - Threaded
8	45662C	Push Button
9	45738C	Push Button Sleeve
10	45736C	Nut - Regulator Mounting
11	1000004652	Bubbler Assy VR
12	56087C	Push Button - Extension
13	56053C	Fountain - Galaxy Gray (HRFG-E)
	55969C	Fountain - Galaxy Gray (HRFG-S)
14	56301C	Panel - Dbl Back Galaxy Gray
15	75672C	Screw - Cap #6-32 X 5/16
16	55996C	In-Line Strainer
NS	75520C	T-25 Pinned Torx Bit





FIG. 7

PRODUCT SPECIFICATIONS

Elkay Soft Sides® Bi-Level Composite Fountain Non-Filtered Non-Refrigerated White Granite Composite. Furnished with Vandal Resistant bubbler. Mechanical Front Bubbler Button activation. Product shall be Wall Mount (On Wall), for Indoor + Outdoor applications, serving 2 station(s). Unit shall be lead-free design which is certified to NSF/ANSI 61 & 372 (lead free) and meets Federal and State low-lead requirements.

Finish:	White Granite Composite (WH)
Power:	No Electrical Required
Bubbler Style:	Vandal Resistant
Activation by:	Mechanical Front Bubbler Button
Mounting Type:	Wall Mount (On Wall)
Chilling Capacity:	Non-refrigerated
Dimensions (L x W x H):	38-1/2" x 18-13/16" x 20-3/8"
Approx. Shipping Weight:	97 lbs.
Installation Location:	Indoor + Outdoor
No. of Stations Served:	2
**When used in non-temperature controlled environments, unit(s) must be adequately winterized and/or protected from extreme heat to prevent damage where climates dictate.	

- Mechanically-Activated bubbler continues to supply water in event of service disruptions.
- With a contemporary look and smooth, rounded lines, these wall mounted drinking fountains are constructed of a premium composite, solid surface material.



White (WHT)

Included with Product: Fountain Ships in one box.

A Century of Tradition and Quality. For more than 100 years, Elkay has been making innovative products and providing exceptional customer care. We take pride in offering plumbing products that make life easier, inspire change and leave the world a better place.



PRODUCT COMPLIANCE

ADA & ICC A117.1

Buy American Act

NSF/ANSI 61 & 372 (lead free)



Complies with ADA & ICC A117.1 accessibility requirements when installed according to the requirements outlined in these standards. Installation may require additional components and/or construction features to be fully compliant. Consult the local Authority Having Jurisdiction if necessary.

[Installation Instructions \(PDF\) - 98409C](#)

Water Systems are warranted for 12 months from date of installation.

Warranty pertains to drinking water applications only. Non-drinking water applications are not covered under warranty.

[Warranty \(PDF\)](#)

PART: _____ QTY: _____

PROJECT: _____

CONTACT: _____

DATE: _____

NOTES: _____

APPROVAL: _____

In keeping with our policy of continuing product improvement, Elkay reserves the right to change product specifications without notice. Please visit elkay.com for the most current version of Elkay product specification sheets. This specification describes an Elkay product with design, quality, and functional benefits to the user. When making a comparison of other producers' offerings, be certain these features are not overlooked.


Optional Accessories		
EWF172	Elkay WaterSentry VII Filter Kit (Coolers + Fountains) Spec Sheet (PDF)	
MPW200	In-wall Mounting Plate for Bi-level On-wall Non-refrigerated Fountains Spec Sheet (PDF)	
ACCESS12X38-5	Stainless Steel Access Panel for Bi-Level Architectural Fountains Spec Sheet (PDF)	

In keeping with our policy of continuing product improvement, Elkay reserves the right to change product specifications without notice. Please visit elkay.com for the most current version of Elkay product specification sheets. This specification describes an Elkay product with design, quality, and functional benefits to the user. When making a comparison of other producers' offerings, be certain these features are not overlooked.



INSTALLER NOTE

This drinking fountain is furnished with a bubbler and valve including all connecting fittings which are manufactured of completely lead free material. Shut off valve (not furnished) to accept 3/8" O.D. unplated copper tube.

OPERATION OF QUICK CONNECT FITTINGS




PUSHING TUBE IN BEFORE PULLING IT OUT HELPS TO RELEASE TUBE



LEGEND

- A = 7/8" (22mm) Ø Hole for water supply tube
- B = 1-3/4" (44mm) Ø Hole for waste line
- C = 1/2" (13mm) Ø Clearance hole for mounting

In keeping with our policy of continuing product improvement, Elkay reserves the right to change product specifications without notice. Please visit elkay.com for the most current version of Elkay product specification sheets. This specification describes an Elkay product with design, quality, and functional benefits to the user. When making a comparison of other producers' offerings, be certain these features are not overlooked.



In keeping with our policy of continuing product improvement, Elkay reserves the right to change product specifications without notice. Please visit elkay.com for the most current version of Elkay product specification sheets. This specification describes an Elkay product with design, quality, and functional benefits to the user. When making a comparison of other producers' offerings, be certain these features are not overlooked.



Product Materials

Flanges: 3 $\frac{1}{8}$ " dia. 11 gauge stainless steel with exposed surfaces in architectural satin finish.

Tubing: 1 $\frac{1}{2}$ " O.D. 18 gauge stainless steel, seamless construction with exposed surfaces in architectural satin finish. Bent ends of tubing pass thru the flanges and are welded into a single structural unit for maximum strength. Intermediate supports are contour cut and joined by welding to form an integral part of the grab bar. All exposed welds ground and polished to blend. Mandrel bending process maintains uniform bar diameter. Return provides 1 $\frac{1}{2}$ " standard safety clearance between wall and bar.

Strength

When properly mounted, all Bradley heavy-duty grab bar systems meet or exceed the requirements of ANSI Standard A117.1, the ADA and ABA Accessibility Guidelines for Buildings and Facilities (ADAAG), and the Uniform Federal Accessibility Standard (UFAS). Select dimensions of configurations are 3rd party tested to support up to 1000 pounds. See configurations on following page. All other 817 grab bars outside of these parameters are rated to support up to 250 pounds. Wall must be reinforced in the area of the grab bar in order to support the load it is intended to support.

Guide Specification

Grab bar shall be fabricated of satin finish stainless steel with exposed mounting flanges in sizes and configurations as indicated. Install with Bradley Mounting Kits as indicated.

Installation


Please visit www.bradleycorp.com for instructions on installation, warnings, and maintenance.

ADA Compliant

- ☒ Consult local and national accessibility codes for proper installation guidelines.
- ☒ Conformity and compliance to local and national codes is the responsibility of the installer.

Optional Features

Features	Suffix
Safety-Grip Finish	-2
High-Polish Finish	-4
Safety Grip with High-Polished Finish	-7



Bradex® Models

Configuration Number	Shipping Data	
	Cu. Ft.	Wt. Lb.
001-36"	0.15	3
001-42"	0.15	4

Orders composed of products indicated as **Bradex®** will be available to ship in three days after receipt of order at the factory. There is no pricing penalty for this service from Bradley.









Configuration Information

OD		1-1/2"
Rating (LBS)		1000
Configuration Number	Grab Bar Length	817 Series
001-12	12"	X
001-18	18"	X
001-24	24"	X
001-36	36"	X
001-48	48"	X
001-54	54"	X
059/058	up to 42" x 54"	X
054	33" x 30"	X
055	24" x 24"	X
060	36" x 60" x 36"	X

WARNING Only models/configurations listed on this page have been rated for use up to 1000 pounds. Please see [Grab Bar Configurations on bradleycorp.com](https://www.bradleycorp.com) for all other available configurations.

Bradex® Item - Standard Finish

Bradex® Item - Standard Finish or Safety Grip Finish (-2)



Orders composed of products indicated as **Bradex®** will be available to ship in three days after receipt of order at the factory. There is no pricing penalty for this service from Bradley.



2902-2800, 2902-2873, 2902-2874, 2902-2878

Adjustable Motor, Adjustable Sensor-Operated Warm Air Hand Dryer

☒ Recommended for very high traffic areas.

Standard Model 2902-280000 (cast iron white porcelain) *Bradex*

Standard Model 2902-287300 (steel-white epoxy) *Bradex*

Standard Model 2902-287400 (stainless steel-satin finish) *Bradex*

Standard Model 2902-287800 (stainless steel-bright polished finish)

Product Materials

2902-2800 COVER: 3/16" (4.5 mm) thick one-piece cast iron; white porcelain enamel coating.

2902-2873 COVER: 1/16" (1.5mm) thick one-piece steel; white epoxy finish.

2902-2874 COVER: 1/16" (1.5mm) thick one-piece stainless steel; satin finish.

2902-2878 COVER: 1/16" (1.5mm) thick one-piece stainless steel; bright polished finish.

Cover fixed to the base plate with two vandal-proof lock screws and lock with special key wrench.

ADJUSTABLE MOTOR: universal-type with high-speed, universal brush, fully adjustable (3,800–8,200 RPM) potentiometer, Class A; Aluminium centrifugal double asymmetrical inlet fan wheel; aluminum scroll fan and safety thermal cut-off.

HEATING ELEMENT: waved wire NiCr heating element mounted on a mica frame that incorporates a self-resetting thermal cut-off at 302°F.

ADJUSTABLE SENSOR OPERATION: electronic infrared detection sensor with fully adjustable (2"–8") potentiometer. Includes polycarbonate viewing windows. Automatic shut-off after 60 seconds.

BASE PLATE: 1/8" (3 mm) thick aluminum, with four Ø 5/16" (8 mm) holes for wall mounting. Includes silent blocking to dampen mechanical vibrations.

Installation

Verify all rough-in dimensions prior to installation. Hand dryers require a dedicated circuit and must be properly grounded. GFI Circuit protection is recommended. One side of dryer should be mounted to a stud.

Operation

Place hands 3"–6" below nozzle to activate air flow. Dryer will stop two seconds after hands are removed from air flow.

ADA Compliant

- ☒ Consult local and national accessibility codes for proper installation guidelines.
- ☒ Conformity and compliance to local and national codes is the responsibility of the installer.

Orders composed of products indicated as **Bradex** will be available to ship in three days after receipt of order at the factory. There is no pricing penalty for this service from Bradley.



Guide Specification

Surface-mounted ADA-compliant hand dryer shall have a thick cast iron cover with white porcelain enamel coating (2902-2800), steel cover with white epoxy coating (2902-2873), stainless steel cover with satin finish (2902-2874) or stainless cover with bright polished finish (2902-2878). Hand dryer shall include aluminium base plate, fully adjustable (2"–8") infrared sensor potentiometer and fully adjustable (3800 - 8200 RPM) universal-type motor potentiometer with resilient mounts and sealed, lubricated ball bearings. Dryer shall operate at 64–70 dB while delivering 43–70 CFM of air at 106°F–111°F (41°C–44°C) and 4,920–9,840 LFM velocity during user-controlled drying cycle. Dryer shall have a total power of 800–1,150 W (1.07–1.54 Hp) with a consumption of 9.5–4.8 A.

Overall dimensions: 10½"H x 11½"W x 4"D (267mm x 292mm x 102mm).

Weight: 7.9 lb (3.58 kg)

Product Specifications

Voltage:	100–120 V, 208 V, 220–240 V	Consumption:	9.5–4.8 A
Motor:	1/2 HP (250 W)	RPM:	3,800–8,200
Nominal power:	1,150 W (1.54 Hp)	Heating element:	900 W (1.20 Hp)
Effective airflow:	36–58 CFM	Nominal airflow:	43–70 CFM
Noise level at 79":	64–70 dB	Airspeed:	4,920–9,840 LFM
Frequency:	50/60 Hz	Insulation:	Grounding required
Temperature (at 4" distance / 70°F):	106°F–111°F (41°C–44°C)	Certificates:	UL 499 / CSA C22.2 / VDE GS / VDE EMC / GMark
Drying time:	12–15 seconds	Mounting:	Surface. ADA-compliant
Protection level:	IP23 Splash Protection		




2902-2800, 2902-2873, 2902-2874, 2902-2878

Adjustable Motor, Adjustable Sensor-Operated Warm Air Hand Dryer

Dimensions

(mm)



Dim. "A" Key Surface:	For Dim. "A"	Top of Unit	Bottom of Unit
Sensor top to finished floor	48" (1219)	$57\frac{3}{4}"$ (1467)	$47\frac{1}{8}"$ (1197)
	45" (1143)	$54\frac{3}{4}"$ (1391)	$44\frac{1}{8}"$ (1121)
	42" (1067)	$51\frac{3}{4}"$ (1314)	$41\frac{1}{8}"$ (1045)
	40" (1016)	$49\frac{3}{4}"$ (1264)	$39\frac{1}{8}"$ (994)
Rough wall opening:			
Surface Mount:	No rough opening, see overall dimensions		

Orders composed of products indicated as **Bradex**® will be available to ship in three days after receipt of order at the factory. There is no pricing penalty for this service from Bradley.

Page 2 of 2
This information is subject to change without notice.
Bradley_HandDryer_2902-2800_2873_2874

5/12/2021

[View Latest Version](#)

© 2021 Bradley
P.O. Box 309, Menomonee Falls, WI 53052-0309
800 BRADLEY (800 272 3539) +1 262 251 6000
bradleycorp.com



MG-2

Express® Lavatory System – MG-Series

- ADA and TAS compliant
- Serves one or two users at a time
- Standard lavatory spacing on 30" centers
- Continuous bowl, sprayhead, and end caps are constructed of Terreon® or Terreon®RE solid surface material
- Available in a variety of colors
- Available in infrared, air valve metering, or TouchTime® mechanical metering

Specifications

The flowing "wave" design accommodates one to two users. Units handle washroom traffic quickly and economically, while providing each user with personal space. Lavatories for the system are positioned on 30" centers. Bradley's continuous bowl features a contemporary flowing "wave" design. This unique "wave" pattern is repeated in the sprayhead, integrating the components. The pre-assembled sprayhead module is equipped with independent aerators, each served by separate infrared sensing module and solenoid valve (Model MG-2/IRP), pushbutton air metering valve (Model MG-2/AST4), TouchTime® mechanical pushbutton (Model MG-2/TTPA) or TouchTime piezo switch (MG-2/TTPB), or independent battery IR sensor and batteries (Model MG-2/BIR3). Operating range is 20–80 psi. Flow restrictor keeps flow rate constant at all pressures.

Product Compliance

Listed by IAPMO R&T to

- Uniform Plumbing Code (UPC)
- National Plumbing Code of Canada
- International Plumbing Code (IPC)
- IGC 156 and the requirements of CSA B45.5/IAPMO Z124 and ASME A112.18.1/CSA B125.1



Listed by UL Environment to

- GreenGuard Gold



Serves the American Disabilities Act and ICC/ANSI 117.1 guidelines, citations 306, 308, 309.4, 606.4, 606.5 when installed according to these requirements. Consult local codes and standards.



This plumbing fixture is designed for hand washing only. It is not intended to dispense water for human consumption through drinking or for preparation of food or beverages.

Verify all rough-in dimensions prior to installation.

Consult local and national codes. Conformity and compliance to local and national codes is the responsibility of the installer.

Page 1 of 5

1/20/2021

[View Latest Version](#)

This information is subject to change without notice.

Bradley_Sink_Express_MG-2



Construction

Bowl, Sprayhead, and Pedestal End Caps

Constructed of Terreon, a densified solid surface material composed of a bio-based resin, or TerreonRE, a densified solid surface material composed of a bio-based resin and preconsumer recycled granules. Terreon and TerreonRE are resistant to chemicals, stains, burns, and impact. Surface damage can be easily repaired with everyday cleansers or fine grit abrasives. Terreon and TerreonRE are GREENGUARD® certified as low-emitting materials.

Support Frame and Access Panel

Bowl assembly and pedestal end caps are secured to a heavy gauge stainless steel support frame mounted to the wall. The contoured front access panel is constructed of 300 series stainless steel.

Vandal Resistance

The molded solid surface sprayhead is an integral part of the bowl module. A free-spinning collar protects the aerator from vandalism. The infrared sensor will automatically shut off water flow after 30–45 seconds if a vandal attempts to trigger constant operation by covering the sensor, or by placing a stationary object in the sensor's detection area. Pushbuttons are secured to the unit from inside the sprayhead. Air valves, water supplies, and waste are concealed within the pedestal/support frame assembly.

Standard Equipment

Continuous bowl with two lavatories, sprayhead, pedestal, stainless steel mounting frame (as described above), 120VAC/12VDC plug-in adapter (Model MG-2/IRP, Model MG-2/TTPA and Model MG-2/TTPB). Batteries are included (Model MG-3/BIR3). The following fittings are provided: P-trap, tailpiece, two flexible stainless steel supply connections, and Navigator® thermostatic mixing valve with stops.

© 2021 Bradley

P.O. Box 309, Menomonee Falls, WI 53052-0309
800 BRADLEY (800 272 3539) +1 262 251 6000
bradleycorp.com



MG-2

Express® Lavatory System – MG-Series

Activation Types

Infrared (Model MG-2/IRP)

The sensor module uses a conical infrared transmitting beam, creating a wide detection area. Adaptive-style sensor shall learn installation environment upon power-up and react (activate) when the user's hands enter the detection area. Each of the aerators is controlled by a separate, slow-closing solenoid valve. Hands placed within the bowl are detected and will activate a flow of tempered water at a rate of 0.50 gpm (1.9 Lpm). A timing turn-off delay of 2–3 seconds results in a smooth, controlled hand-washing operation. The Bradley adaptive sensor is not affected by varying color tones or darkness. Direct sunlight or bright washroom lights (up to 10,000 foot candles) will not activate the system.

- Solenoids – 12VDC, 3/8" NPT. The electronically activated, slow-closing solenoid valve provides reliable performance since there are few moving parts, and its operation is unaffected by most chemicals and minerals often present in municipal water supplies. Neither the solenoid valve nor the infrared sensor module need adjustment for range or timing.
- Low Voltage Plug-In Adapter – A UL/CSA-listed 120VAC/12VDC plug-in adapter powers the solenoid valves. The plug-in adapter, furnished as standard equipment, plugs into a standard GFCI protected electrical outlet.

Battery Infrared (Model MG-2/BIR3)

Each battery-powered sensor uses a zone-focused infrared transmitting beam, creating a large detection area. The sensor is not affected by varying skin tones or darkness. When hands enter the detection area, the sensor starts water flow by opening the valve electronically. Tempered water flows at a rate of 0.50 gpm (1.9 Lpm). When hands leave the detection area, the sensor stops the flow of water by closing the valve. The 6VDC, electronically activated solenoid valve has few moving parts, providing reliable operation that is unaffected by most chemicals and minerals often present in municipal water supplies. Each station is powered by a single lithium battery. Battery type is Duracell® DL 223A 6V lithium or equivalent (batteries included) with a life expectancy of 4–5 years or approximately 200,000 cycles.

Air Valve Metering (Model MG-2/AST4)

Each pushbutton pneumatically actuates a non-hold-open air metering, single-temperature valve with field adjustable timing from 0–45 seconds. Factory set at 11 seconds. Each pushbutton activates one valve which, in turn, activates one hand washing station at a rate of 0.10 gpc (0.38 Lpc). Push button requires less than five pounds of pressure.

TouchTime® Mechanical Metering (Models MG-2/TTPA & MG-2/TTPB)

Each low voltage mechanical pushbutton or piezo switch actuates a non-hold-open, slow closing anti-hammer solenoid valve that is timed from an electronic potted assembly. Each push button activates one valve, which, in turn, activates one station flowing tempered water at a rate of 0.10 gpc (0.38 Lpc). TouchTime controls water flow at each station through the use of solid-state, digital circuitry. Timing is factory set at a 15 second run time but is field adjustable to pre-set timeout periods and optional auto-flush function. The 24 hour flush function will activate water flow for a period of 60 seconds any time there has been no activation within the past 24 hours. Push button requires less than five pounds of pressure.

Optional Equipment

Soap Dispenser Type

One horizontally-mounted pump-style valve is located over the drain. Soap tank is located within the stainless steel frame. Soap tank is refillable through an easily accessible exterior filler cap. Filler cap is vandal resistant and opens with special spanner wrench included. Soap tank capacity is ¾ gallon.

For information on Terreon and TerreonRE Waste Receptacles for the Express MG-Series, visit bradleycorp.com.

Verify all rough-in dimensions prior to installation.

Consult local and national codes. Conformity and compliance to local and national codes is the responsibility of the installer.

Page 2 of 5

1/20/2021

[View Latest Version](#)

This information is subject to change without notice.

Bradley_Sink_Express_MG-2

© 2021 Bradley
P.O. Box 309, Menomonee Falls, WI 53052-0309
800 BRADLEY (800 272 3539) +1 262 251 6000
bradleycorp.com




MG-2 Express® Lavatory System – MG-Series


Dimensions

(mm)


Top View



Front View



Side View



* Subtract 4" from all vertical dimensions for Juvenile Height Mounting.

* Subtract 3½" from all vertical dimensions for TAS Juvenile Height Mounting (grades Pre-K through 5 or 6).

* Subtract 1½" from all vertical dimensions for TAS Juvenile Height Mounting (grades 6 through 8 or 9).

Verify all rough-in dimensions prior to installation.

Consult local and national codes. Conformity and compliance to local and national codes is the responsibility of the installer.

Page 3 of 5

1/20/2021

[View Latest Version](#)

This information is subject to change without notice.

Bradley_Sink_Express_MG-2

© 2021 Bradley

P.O. Box 309, Menomonee Falls, WI 53052-0309

800 BRADLEY (800 272 3539)

+1 262 251 6000

bradleycorp.com



MG-2 Express® Lavatory System – MG-Series

Rough-Ins

(mm)

Mounting for Standard Height Is Shown




Chart 1

Std. Height	Vertical Height Adjustments Codes A, B, C, D, E, F and G	Fixture Style
*	None	Standard Height
*	Subtract 4"	Juvenile Height
*	Subtract 1 1/2"	TAS, Grades 6 through 8 or 9
*	Subtract 3 1/2"	TAS, Pre-K through Grades 5 or 6

Chart 2

Code	Description	Qty.
A	3/8" Wall Anchors with a minimum pull out force of 1,000 lb	8
B	1/2" Nominal Copper Tubing for Hot Supply, Stub-Out 2" from Wall	1
C	1/2" Nominal Copper Tubing for Cold or Tempered Supply, Stub-Out 2" from Wall	1
D	1 1/2" NPT Drain, Stub-Out 2" from Wall	1
E	110V GFCI Protected Electrical Outlet. I.R. and TouchTime Only	1

Verify all rough-in dimensions prior to installation.

Consult local and national codes. Conformity and compliance to local and national codes is the responsibility of the installer.

Page 4 of 5 1/20/2021

[View Latest Version](#)

This information is subject to change without notice.

Bradley_Sink_Express_MG-2

© 2021 Bradley
P.O. Box 309, Menomonee Falls, WI 53052-0309
800 BRADLEY (800 272 3539) +1 262 251 6000
bradleycorp.com



MG-2

Express® Lavatory System – MG-Series

Standard Selections (Must select one from each category)			
Activation Type			
IRP	Infrared		
AST4	Air Pushbutton		
TTPA	TouchTime Pushbutton		
TTPB	TouchTime Piezo Switch		
BIR3	Battery Infrared		
Soap Dispenser Type (select one)			
LSD-2	One Integral Liquid Soap Dispenser (MG-2)		
NSD	No Soap Dispenser		
Water Supply Type (select one)			
TMA	Navigator Thermostatic Mixing Assembly (Hot and Cold Supplies)		
TL	Single Tempered Line		
Color of Terreon Bowl/Sprayhead Cover (select one)			
<i>Standard Colors</i>			
ALP-WHT	Alpine White	LONDON	London Gray
AVALANCHE	Avalanche †	MOONSTONE	Moonstone †
BONE	Mesa Bone	O-TAUPE	Organic Taupe
CHAR	Charcoal Gray	PEBBLE	Pebble Beach
COBBLE	Cobblestone	PEP-WHT	Peppered White
DRIFT	Driftwood †	POLAR	Polar Ice †
DS-WHT	Designer White	SAND	Sandtrap
DUNE	Sand Dune †	S-CREEK	Stone Creek
E-GRAY	Empire Gray	S-MIST	Silver Mist
GLACIER	Glacier	WHT-SAND	White Sand
GRAPH	Graphite		
LANNON	Lannonstone		
<i>Designer Colors* (available at an additional charge)</i>			
ARC-CHIP	Arctic Chip	COFFEE	Coffee Bean
RIVER	Riverstone		
<i>TerreonRE Colors* (available at an additional charge)</i>			
BIRCH-BARK	Birch Bark	MOONDUST	Moondust
DUSK	Dusk	OAT	Oat
Optional Selections			
Waste Assembly Type:			
S-CHROME	Single Chrome-Plated P-Trap		
S-POLY	Single Polypropylene P-Trap		

*Non-cancelable, non-returnable

† This color contains large, randomly distributed chips.

Verify all rough-in dimensions prior to installation.

Consult local and national codes. Conformity and compliance to local and national codes is the responsibility of the installer.

Page 5 of 5

1/20/2021

[View Latest Version](#)

This information is subject to change without notice.

Bradley_Sink_Express_MG-2

© 2021 Bradley
P.O. Box 309, Menomonee Falls, WI 53052-0309
800 BRADLEY (800 272 3539) +1 262 251 6000
bradleycorp.com

Lucerne™ Wall-Hung Lavatory

- Wall-hung sink
- Vitreous china
- Front overflow
- D-shaped bowl
- Self-draining deck area with contoured back and side splash shields
- Faucet ledge
- Compliant with Texas Accessibility Standard (TAS) for children age group 13 and up

Faucet holes on 203 mm (8") centers:

- ☐ **0356.028** For exposed bracket support (by others)
- ☐ **0356.015** For wall hanger (included) or concealed arms support (by others)
- ☐ **0356.915** For wall hanger (included) or concealed arms support (by others) less overflow
- ☐ **0356.037** For wall hanger (included) or concealed arms support (by others) with extra 35 mm (1-3/8") hole for soap/lotion dispenser (by others) on right-hand side

Faucet holes on 102 mm (4") centers:

- ☐ **0355.027** For exposed bracket support (by others)
- ☐ **0355.012** For wall hanger (included) or concealed arms support (by others)
- ☐ **0355.912** For wall hanger (included) or concealed arms support (by others) less overflow
- ☐ **0355.056** For wall hanger (included) or concealed arms support (by others) with extra 35 mm (1-3/8") hole for soap/lotion dispenser (by others) on left-hand side
- ☐ **0355.034** For wall hanger (included) or concealed arms support (by others) with extra 35 mm (1-3/8") hole for soap/lotion dispenser (by others) on right-hand side
- ☐ **0355.041** With two holes spaced 343 mm (13-1/2") in back splash for 10 mm (3/8") bolts (by others)

Single center faucet hole:

- ☐ **0356.041** For exposed bracket support (by others)
- ☐ **0356.421** For wall hanger (included) or concealed arms support (by others)
- ☐ **0356.921** For wall hanger (included) or concealed arms support (by others) less overflow
- ☐ **0356.439** For wall hanger (included) or concealed arms support (by others) with single faucet hole on right
- ☐ **0356.066** For exposed bracket support (by others) with single faucet hole on right
- ☐ **0356.115** For wall hanger (included) or concealed arms support (by others) with extra 35 mm (1-3/8") hole for soap/lotion dispenser (by others) on left-hand side
- ☐ **0356.137** For wall hanger (included) or concealed arms support (by others) with extra 35 mm (1-3/8") hole for soap/lotion dispenser (by others) on right-hand side



0355.012



0356.041

SEE FOLLOWING PAGES FOR ROUGHING-IN DIMENSIONS

Compliance Certifications - Meets or Exceeds the Following Specifications:

- ASME A112.19.2 / CSA B45.1 for Vitreous China Fixtures

Nominal Dimensions:

540 x 464 mm
(21-1/4" x 18-1/4")

Bowl sizes:


379 mm (14-7/8") wide
254 mm (10") front to back
165 mm (6-1/2") deep

To Be Specified:

- ☐ Color: ☐ White
- ☐ Faucet:
- ☐ Faucet Finish:
- ☐ Supplies:
- ☐ 1-1/4" Trap:
- ☐ Bracket Support (by others):
- ☐ Concealed Arms Support (by others):


8" CENTER CONFIGURATIONS

All Wall Hanger (included) or Concealed Arm Configurations




4" CENTER CONFIGURATIONS

All Wall Hanger (included) or Concealed Arm Configurations



SIDE VIEW - ALL CONFIGURATIONS



NOTES:

* DIMENSIONS SHOWN FOR LOCATION OF SUPPLIES AND "P" TRAP ARE SUGGESTED. PROVIDE SUITABLE REINFORCEMENT FOR ALL WALL SUPPORTS. FITTINGS NOT INCLUDED AND MUST BE ORDERED SEPARATELY. CONCEALED ARM SUPPORT AS REQUIRED TO BE FURNISHED BY OTHERS.

IMPORTANT: Dimensions of fixtures are nominal and may vary within the range of tolerances established by ANSI Standard A112.19.2. These measurements are subject to change or cancellation. No responsibility is assumed for use of superseded or voided pages.




MEETS THE AMERICANS WITH DISABILITIES ACT GUIDELINES AND ANSI A117.1 ACCESSIBLE AND USABLE BUILDINGS AND FACILITIES - CHECK LOCAL CODES.

Top of front rim mounted 864mm (34") from finished floor.


SINGLE CENTER HOLE CONFIGURATIONS

All Wall Hanger (included) or Concealed Arm Configurations



SINGLE CENTER HOLE ON RIGHT CONFIGURATIONS

All Wall Hanger (included) or Concealed Arm Configurations



NOTES:

* DIMENSIONS SHOWN FOR LOCATION OF SUPPLIES AND "P" TRAP ARE SUGGESTED. PROVIDE SUITABLE REINFORCEMENT FOR ALL WALL SUPPORTS. FITTINGS NOT INCLUDED AND MUST BE ORDERED SEPARATELY. CONCEALED ARM SUPPORT AS REQUIRED TO BE FURNISHED BY OTHERS.

IMPORTANT: Dimensions of fixtures are nominal and may vary within the range of tolerances established by ANSI Standard A112.19.2. These measurements are subject to change or cancellation. No responsibility is assumed for use of superseded or voided pages.



MEETS THE AMERICANS WITH DISABILITIES ACT GUIDE-
LINES AND ANSI A117.1 ACCESSIBLE AND USABLE
BUILDINGS AND FACILITIES - CHECK LOCAL CODES.

Top of front rim mounted 864mm (34") from finished floor.

**Mirror with roll-formed channel frame and theft-resistant mounting:**

- ☐ Standard Model 781-1824 (18" x 24") **Bradex**[®]
- ☐ Standard Model 781-1830 (18" x 30") **Bradex**[®]
- ☐ Standard Model 781-1836 (18" x 36") **Bradex**[®]
- ☐ Standard Model 781-18362 (18" x 36", tempered glass) **Bradex**[®]
- ☐ Standard Model 781-2430 (24" x 30") **Bradex**[®]
- ☐ Standard Model 781-2436 (24" x 36") **Bradex**[®]
- ☐ Standard Model 781-24362 (24" x 36", tempered glass) **Bradex**[®]
- ☐ Standard Model 781-2448 (24" x 48") **Bradex**[®]
- ☐ Standard Model 781-2460 (24" x 60") **Bradex**[®]
- ☐ Model 781-XXXX (Specify width and height)

Product Materials

FRAME: one-piece, roll-formed stainless steel with bright annealed finish. Channel is $\frac{3}{4}$ " x $\frac{3}{4}$ " x $\frac{7}{16}$ " with 90° mitered corners. Double strength continuous integral stiffener on all sides for added strength.

BACK: galvanized steel.

MIRROR: first quality $\frac{1}{4}$ " float glass, thermosetting infrared cured paint backing with Poly-Glaze protective finish. Manufactured in accordance with ASTM C 1036 and ASTM C 1503. All edges protected by shock-absorbing, neoprene tubing. The back of the mirror is protected by a sheet of $\frac{1}{4}$ " extruded polystyrene, which is placed between the mirror and the galvanized steel.

MOUNTING BRACKETS: 18 gauge cold rolled steel.

Optional Features

Features	Suffix
☐ $\frac{1}{4}$ " tempered glass mirror in lieu of polished float glass mirror*	-2
☐ Laminate glass	-3
☐ Highly polished No. 8 architectural finish, 20 gauge stainless steel in lieu of polished float glass mirror	-4
☐ Bright annealed 20 gauge stainless steel in lieu of polished float glass mirror	-5
☐ Plexiglas [®]	-6

*Either the Length (L) or the Width (W) must be greater than 25".

- ☒ An inherent characteristic of a manufacturing process for tempered glass is distortion which may vary from mirror to mirror.
- ☒ Stainless steel mirrors will differ in optic quality from glass mirrors.
- ☒ In larger sizes, stainless mirrors are subject to distortion and/or "oil canning" for which Bradley Corporation cannot accept responsibility.
- ☒ Bradley mirrors are not field interchangeable from horizontal to vertical or vice versa.
Always specify width first.

Orders composed of products indicated as **Bradex**[®] will be available to ship in three days after receipt of order at the factory. There is no pricing penalty for this service from Bradley.

Page 1 of 2 7/17/2017
This information is subject to change without notice.
Bradley_Mirror_781

**Installation**

Verify all rough-in dimensions prior to installation. Secure concealed mounting bracket to wall with screws (not included) at holes provided. Mounting kits available through Bradley (ref. #899-026). For more information, visit bradleycorp.com. Provide in-wall backing at mounting screw locations. Position mirror over mounting bracket to engage hanger tabs. Slide mirror down and lock into position.

Guide Specification

Mirror shall be framed with one-piece, roll-formed stainless steel with $\frac{3}{4}$ " face and neatly mitered corners. Double -strength continuous integral stiffener on all sides. Back of unit shall be galvanized steel. Separate brackets for concealed mounting. Mirror shall be of first quality $\frac{1}{4}$ " polished float glass, guaranteed for 15 years against silver spoilage and protected by shock-absorbing, neoprene tubing with Poly-Glaze protective finish.

Framed Mirror shall be Bradley Model
781-_____ " W x _____ " H (specify width and height).


ADA Compliant

- ☒ Consult local and national accessibility codes for proper installation guidelines.
- ☒ Conformity and compliance to local and national codes is the responsibility of the installer.





Dimensions

MIRRORS 30" WIDE AND UNDER



MIRRORS OVER 30" WIDE

**Bradex® Models**

Width (Inches) W	Height (Inches) H	Overall Dimension (Inches)	Overall Dimensions (Millimeters)	Standard Model Number
18"	24"	18 x 24	457 x 610	781-1824
18"	30"	18 x 30	457 x 762	781-1830
18"	36"	18 x 36	457 x 914	781-1836
18"	36"	18 x 36	457 x 914	781-18362
24"	30"	24 x 30	610 x 762	781-2430
24"	36"	24 x 36	610 x 914	781-2436
24"	36"	24 x 36	610 x 914	781-24362
24"	60"	24 x 60	610 x 1524	781-2460
24"	48"	24 x 48	610 x 1219	781-2448
36"	36"	36 x 36	914 x 914	781-3636

Model 781 series channel-framed mirrors can be fabricated to fit a maximum size of 120"W x 72"H but must not exceed 40 sq ft.

Dim. "A" Key Surface:	For Dim. "A"	Bottom of Unit
Mirror's bottom edge of the reflecting surface to finished floor	40" (1016mm)	39 1/4" (997mm)
	37" (940mm)	36 1/4" (921mm)
	34" (864mm)	33 1/4" (845mm)
Rough wall opening:		
Surface Mount:	No rough wall opening, see overall dimensions	

Orders composed of products indicated as **Bradex®** will be available to ship in three days after receipt of order at the factory. There is no pricing penalty for this service from Bradley.



Restroom Partitions, Floor-Mounted with Overhead-Brace

Bradmar® Solid Plastic (HDPE) — Series 400 – Sentinel™

This is the most popular style of partitions. It is attached to the floor and stabilized at the top of the pilaster with anti-grip headrail. Floor-mounted overhead-braced material is recommended for heavy traffic or vandalism-prone areas. It does not require any special floor or ceiling construction, which makes it suitable for new or existing construction. (Partitions must be installed in a climate-controlled environment, away from direct sunlight.)

Construction

Doors, panels and pilasters are constructed from 1" thick High Density Polyethylene (HDPE) resins pressed under high pressure to form a single component. This material is waterproof, non-absorbent and has a self-lubricating surface which resists marks from graffiti. All plastic components are shipped with a self-adhesive coating for protection during installation. Bradmar® is available in a variety of colors.

Panels and Doors

Panels and doors are fabricated 55" high, all edges are rounded to a $\frac{3}{16}$ " radius. Panels and doors receive an aluminum heat sink strip fastened to the bottom edge which helps dissipate any applied heat. Each door is pre-drilled to receive an integral hinge assembly. The closing position of each hinge is fully adjustable.

Pilasters

Pilasters are secured through the face of the shoe using Torx-head thru-bolts. 5/16" lag screw(s) (provided in shoe kit) can be added to the floor edge of the pilaster for leveling.

Hardware

Mills standard hardware is constructed from 6463-T-5 heavy-duty aluminum. Compartments are provided with all hardware and stainless steel torx head w/pin fasteners to complete installation for applications with concrete floors and masonry block walls.

Door Hardware

Standard integral hinge system consisting of a $\frac{1}{2}$ " diameter nylon gravity cam unit with a $\frac{3}{16}$ " stainless steel center pin (bottom) and a $\frac{1}{2}$ " nylon rod (top). Latches shall be fabricated from heavy-duty extruded aluminum (6463-T-5 alloy). Slide bolt shall have a black anodized finish. Latch is mounted to the door with stainless steel theft-resistant screws. The slide latch does not require a twisting motion and complies with all Federal ADA guidelines. Strike/keeper is 6" long and is fabricated from heavy-duty extruded aluminum (6463-T-5 alloy) with wraparound flanges. Strike/keeper is mounted to the pilaster with thru-bolts.

Coat hooks, door bumpers and door pulls are provided in a Zamac alloy with satin finish. Integral hinge inswing ADA doors are supplied with an individual coat hook with bumper and double door pull. Integral hinge outswing doors are supplied with individual coat hook, door bumper, and double door pull.

Brackets

Continuous brackets are fabricated from heavy-duty aluminum, are 54" long, and are available in single- or double-ear style.

Headrail

Etched and anodized aluminum headrail is extruded with an anti-grip profile. It clamps over the pilaster and is secured at the wall with plastic brackets.

Shoes

Shoes are 1-piece, 4" high, 300 Series stainless steel with #4 satin brushed finished and are secured to the floor with Torx-head screws.



Series 400 – Sentinel™

Standard Selections (Must select one from each category)

Partition Colors

Beige	Gray
Burgundy	Linen
Buttermilk	Starry Night
Canyon Granite	Toffee
Charcoal Gray	100% Post-Consumer Charcoal*
Deep Blue	100% Post-Consumer Toffee*
Desert Stone	100% Pre-Consumer Black

Door Hardware

Aluminum (STD)
Stainless Steel
Stainless Steel w/Antimicrobial (Integral Hinge only)†

Hinges

Integral (STD)	8" Aluminum Wraparound
Continuous Aluminum Spring Loaded Hinge	
Continuous Stainless Steel Spring Loaded Hinge	

Wall Brackets

Continuous – Aluminum (STD)	Continuous – Stainless Steel
Stirrup Style – Aluminum	

Optional Selections

Miscellaneous

Cutouts

Extra Height

69"/72" H Doors and Panels**

* 100% Post-Consumer HDPE may have some minor flaws and the color may be inconsistent.

† Antimicrobial Components: Door Pull and Latch

** ADA stalls will have 69"H doors and panels, 9" AFF. All other stalls in the room will be 72"H/6" AFF to allow for maximum privacy.

Verify all rough-in dimensions prior to installation.

Consult local and national codes. Conformity and compliance to local and national codes is the responsibility of the installer.

Page 1 of 1 4/10/2019

This information is subject to change without notice.

Bradley_Partitions_Bradmar_OverheadBraced



© 2019 Bradley
P.O. Box 309, Menomonee Falls, WI 53052-0309
800 BRADLEY (800 272 3539) +1 262 251 6000
bradleycorp.com

**Model 583 – Surface-Mounted *Bradex*[®]**

☒ 500 Capacity

Product Materials

COVER: 22 gauge stainless steel with exposed surfaces in architectural satin finish. Welded construction with burr-free edges, full length piano hinge and tumbler lock keyed like other Bradley units.

BACK: stainless steel.

Capacity

500 standard single-fold or half-fold toilet seat covers.

Operation

Cabinet bottom hinged for easy filling. Unit has spring clip dispensing mechanism.

Installation

Verify all rough-in dimensions prior to installation. Secure unit to wall or toilet partition with mounting screws (included) through mounting holes.

Guide Specification

Surface-mounted toilet seat cover dispenser shall be fabricated of 22-gauge stainless steel with exposed surfaces in satin finish with welded construction. Door with piano hinge and tumbler lock. Capacity 500 toilet seat covers.

Overall dimensions: 15"W x 11½"H x 2⅝"D.

**Product Compliance**

- ICC ANSI A117.1, Citation 609.3




- ☒ Consult local and national accessibility codes for proper installation guidelines.
- ☒ Conformity and compliance to local and national codes is the responsibility of the installer.

Orders composed of products indicated as **Bradex**[®] will be available to ship in three days after receipt of order at the factory. There is no pricing penalty for this service from Bradley.



Dimensions

(mm)



Dim. "A" Key Surface:	For Dim. "A"	Top of Unit	Bottom of Unit
Top of seat cover opening to finished floor	48" (1219)	50" (1270)	38 5/8" (981)
	45" (1143)	47" (1194)	35 5/8" (904)
	42" (1067)	44" (1118)	32 5/8" (828)
	40" (1016)	42" (1067)	30 5/8" (777)
Rough wall opening:			
Surface Mount:	No rough opening, see overall dimensions		

Orders composed of products indicated as **Bradex®** will be available to ship in three days after receipt of order at the factory. There is no pricing penalty for this service from Bradley.

CODE NUMBER

3452642

DESCRIPTION

0.5 gpf, Polished Chrome Finish, Fixture Connection Top Spud, Single Flush, True Mechanical Override, Hardwired, Sensor-Operated, Royal® Exposed Sensor Hardwired Urinal Flushometer.

DETAILS

- Flush Volume: 0.5 gpf (1.9 Lpf)
- Finish: Polished Chrome (CP)
- Power Type: Hardwired (HW)
- Valve: Diaphragm
- Valve Body Material: Semi-red Brass
- Fixture Type: Urinal
- Fixture Connection: Top Spud
- Rough-In Dimension: 11 ½" (292mm)
- Spud Coupling: ¾" (19mm)
- Supply Pipe: ¾" (19mm)
- Override: True Mechanical (TMO)

FEATURES


- PERMEX® Synthetic Rubber Diaphragm with Dual Filtered Fixed Bypass
- Handle Packing, Main Seat, Stop Seat and Vacuum Breaker Molded from PERMEX® Rubber Compound for Chloramine resistance
- User friendly three (3) second Flush Delay
- Sweat solder adapter with cover tube and cast wall flange with set screw
- OPTIMA® EL-1500 Self-Adaptive Infrared Sensor with Indicator Light
- "Walk By" Delay of Eight (8) Seconds Prevents Unintentional Flushes
- Non-Hold-Open True Mechanical Override
- Non-Hold-Open Integral Solenoid Operator, Fixed Metering Bypass and No External Volume Adjustment to Ensure Water Conservation
- Courtesy Flush™ Non-Hold-Open True Mechanical Override
- High Back Pressure Vacuum Breaker Flush Connection with One-Piece Bottom Hex Coupling Nut, Spud Coupling and Flange for ¾" Top Spud
- ¾" I.P.S. Screwdriver Bak-Chek® Angle Stop with Vandal Resistant Stop Cap

VIDEOS

- ▶ ESS Flushometer
- ▶ PVD Special Finishes



COMPLIANCES & CERTIFICATIONS



(ADA Compliant, BAA Compliant, BREEAM Water Credit, cUPC Certified, cUPC Green Certified, Green Globes Water Credit, LEED V4 Water Efficiency Credit, Satisfies LEED Credits, UL Certified, WaterSense Listed)

RECOMMENDED SPECIFICATION

Valve Body, Cover, Tailpiece and Control Stop shall be in conformance with ASTM Alloy Classification for Semi- Red Brass. Valve shall be in compliance with the applicable sections of ASSE 1037 and ANSI/ASME 112.19.2.

ELECTRICAL SPECIFICATIONS

- Arming Delay: 8 seconds
- Control Circuit: 24 VAC Input/24 VAC Output/Solid State
- Flush Delay: 3s
- Self-Adaptive Window: ±8
- Sensor Range: 15"-30" (381-762mm)
- Solenoid Operator: 24 VAC
- Transformers (specify separately):
 - 0345154
 - 0345999

VALVE OPERATING PRESSURE (FLOWING)

15-80 PSI (103-552 kPa). Specific fixtures may require greater minimum flowing pressure - consult manufacturer requirements.

DOWNLOADS

- [Royal ESS TMO Installation Instructions](#)
- [Royal ESS Concealed and Exposed Installation Instructions](#)
- [Control Stop Repair and Maintenance Guide](#)
- [Flush Connections Flanges Repair and Maintenance Guide](#)
- [Tail Piece Repair and Maintenance Guide](#)
- [Optima ESS Repair and Maintenance Guide](#)

Sloan 10500 Seymour Ave, Franklin Park, IL 60131

Phone: 800.982.5839 • Fax: 800.447.8329 • sloan.com

- [Additional Downloads](#)

NOTES

All information contained within this document subject to change without notice.


Looking for other variations of the ROYAL 186 ESS product?
[View the general spec sheet with all options.](#)

[Find a compatible urinal](#) for this flushometer.

[Find a compatible water closet](#) for this flushometer.

WaterSense compliant when used with a WaterSense compliant fixture

ROUGH-IN



CODE NUMBER

3450055

DESCRIPTION

1.28 gpf, Polished Chrome Finish, Fixture Connection Top Spud, Single Flush, True Mechanical Override, Sensor-Operated, Royal® Exposed Sensor Hardwired Water Closet Flushometer.

DETAILS

- Flush Volume: 1.28 gpf (4.8 Lpf)
- Finish: Polished Chrome (CP)
- Valve: Diaphragm
- Valve Body Material: Semi-red Brass
- Fixture Type: Water Closet
- Fixture Connection: Top Spud
- Rough-In Dimension: 11 ½" (292mm)
- Spud Coupling: 1 ½" (38mm)
- Supply Pipe: 1" (25mm)
- Override: True Mechanical (TMO)

FEATURES


- PERMEX® Synthetic Rubber Diaphragm with Dual Filtered Fixed Bypass
- Handle Packing, Main Seat, Stop Seat and Vacuum Breaker Molded from PERMEX® Rubber Compound for Chloramine resistance
- User friendly three (3) second Flush Delay
- Sweat solder adapter with cover tube and cast wall flange with set screw
- OPTIMA® EL-1500 Self-Adaptive Infrared Sensor with Indicator Light
- Non-Hold-Open True Mechanical Override
- Die Cast Sensor Plate with no visible Fasteners (for 2-gang Electrical Box)
- 1" I.P.S. Screwdriver Bak-Chek® Angle Stop with Free Spinning Vandal Resistant Stop Cap
- High Back Pressure Vacuum Breaker Flush Connection with One-Piece Bottom Hex Coupling Nut, Spud Coupling and Flange for 1½" Top Spud
- Non-Hold-Open Integral Solenoid Operator, Fixed Metering Bypass and No External Volume Adjustment to Ensure Water Conservation
- "Walk By" Delay of Sixteen (16) Seconds Prevents Unintentional Flushes

VIDEOS

- ▶ ESS Flushometer
- ▶ PVD Special Finishes



COMPLIANCES & CERTIFICATIONS



(ADA Compliant, BAA Compliant, BREEAM Water Credit, cUPC Certified, cUPC Green Certified, Green Globes Water Credit, LEED V4 Water Efficiency Credit, Satisfies LEED Credits, UL Certified, WaterSense Listed)

RECOMMENDED SPECIFICATION

Valve Body, Cover, Tailpiece and Control Stop shall be in conformance with ASTM Alloy Classification for Semi- Red Brass. Valve shall be in compliance with the applicable sections of ASSE 1037 and ANSI/ASME 112.19.2.

ELECTRICAL SPECIFICATIONS

- Arming Delay: 16 seconds
- Control Circuit: Solid State/24 VAC Input/24 VAC Output
- Flush Delay: 3s
- Self-Adaptive Window: ±10
- Sensor Range: 22"-42" (559-1,067mm)
- Solenoid Operator: 24 VAC
- Transformers (specify separately):
 - 0345154
 - 0345999

VALVE OPERATING PRESSURE (FLOWING)

15-80 PSI (103-552 kPa). Specific fixtures may require greater minimum flowing pressure - consult manufacturer requirements.

DOWNLOADS

- [Royal ESS 110/111 Electrical Box Installation Instructions](#)
- [Royal ESS Concealed and Exposed Installation Instructions](#)
- [Royal ESS TMO Installation Instructions](#)
- [Royal 110/111/180/186 ESS TMO \(Spanish\) Installation Instructions](#)
- [Control Stop Repair and Maintenance Guide](#)

Sloan 10500 Seymour Ave, Franklin Park, IL 60131

Phone: 800.982.5839 • Fax: 800.447.8329 • sloan.com

- [Flush Connections Flanges Repair and Maintenance Guide](#)
- [Tail Piece Repair and Maintenance Guide](#)
- [Optima ESS Repair and Maintenance Guide](#)
- [Optima TMO Repair and Maintenance Guide](#)
- [Additional Downloads](#)

NOTES

All information contained within this document subject to change without notice.


Looking for other variations of the ROYAL 111 ESS product?
[View the general spec sheet with all options.](#)

[Find a compatible urinal](#) for this flushometer.

[Find a compatible water closet](#) for this flushometer.

WaterSense compliant when used with a WaterSense compliant fixture

ROUGH-IN



Sloan 10500 Seymour Ave, Franklin Park, IL 60131

Phone: 800.982.5839 • Fax: 800.447.8329 • sloan.com



MADERA™ 15" HEIGHT 1.6 GPF FLUSHOMETER TOILET SYSTEM

with EVERCLEAN®
SELECTRONIC® FLUSH VALVE

MADERA™ 15" HEIGHT 1.6 GPF FLUSHOMETER TOILET SYSTEM with EVERCLEAN®

- ❑ **3451.660** 1.6 gpf 15" Height Top Spud Bowl and Selectronic® Flush Valve

BOWL:

- Floor mount elongated flushometer valve toilet
- Vitreous china
- High Efficiency. Operates in the range of 1.1 gpf to 1.6 gpf (4.2 Lpf to 6.0 Lpf)
- Permanent EverClean® surface inhibits the growth of stain- and odor-causing bacteria, mold, and mildew on the surface
- Fully glazed 2-1/8" trapway
- 10" or 12" rough-in
- 15" rim height
- Condensation channel
- Powerful direct-fed siphon jet action
- 10" x 12" water surface area
- 1-1/2" inlet spud
- 100% factory flush tested
- Less toilet seat
- Model 3451.001

SELECTRONIC® FLUSH VALVE:

- Factory-Installed CR-P2 Lithium Battery
- Self-Cleaning Piston with integral wiper spring significantly reduces clogging and maintenance
- Selectronic® Proximity System with universal sensor provides hygienic, "hands free" operation
- State-of-the-Art Electronics prevent ghost flushing
- Dezincification Resistant semi-red brass alloy
- Fully Mechanical Manual Override Button can flush the valve without power
- Fail-Safe: Valve automatically closes upon loss of power or water pressure and does not need to be reset
- Adjustable Sanitary Flush cleans the fixture & maintains the trap seal.
- Chemical Resistant EPDM Seals for extended life
- Adjustable Tailpiece for rough-in flexibility
- Can be installed left or right handed
- Model 6065.161

Includes:

- 047007-0070A Inlet Spud (furnished with bowl)
- 481310-100 2 Bolt caps with retainers (furnished with bowl)
- 1" I.P.S. angle stop with back-flow protection and vandal-resistant cap
- 1" Sweat solder kit including cover tube and wall flange
- 1-1/2" High back pressure vacuum breaker with spud coupling and flange



SEE REVERSE FOR ROUGHING-IN DIMENSIONS

System MaP* Score:

- 1,000 grams of miso @ 1.6 gpf

* Maximum Performance (MaP) testing performed by IAPMO R&T Lab. MaP Report conducted by Veritec Consulting, Inc. and Koeller and Company.

Operating Pressure:

25 psi (flowing) - 80 psi (static)

Battery Life:

- 4 years @ 4,000 flushes per month

Flow Requirement:

25gpm (94.6 L/min.)

Nominal Fixture Dimensions:

718 x 356 x 381mm (28-1/4" x 14" x 15")

To Be Specified:

- ❑ Color: ☐ White
- ❑ Seat:
 - ❑ American Standard #5901.100 Heavy duty open front less cover
 - ❑ American Standard #5905.100 Extra heavy duty open front less cover

EVERCLEAN®
Surface



MADERA™ 15" HEIGHT 1.6 GPF FLUSHOMETER TOILET SYSTEM


with EVERCLEAN®
SELECTRONIC® FLUSH VALVE

Fixture Compliance Certifications - Meets or Exceeds the Following Specifications:



- ASME A112.19.2-2008 / CSA B45.1-08 for Vitreous China Fixtures

Valve Listings:

- ASSE 1037
- ANSI/ASME A112.19.2
- ADA Compliant



*Note: The Critical Line (-C-L-) on Vacuum Breaker must typically be a minimum of 6" (152mm) above fixture. Consult Codes for details.



VALVE LEFT or RIGHT HAND INSTALLATION

NOTES:

TO COMPLY WITH AREA CODE GOVERNING THE HEIGHT OF VACUUM BREAKER ON THE FLUSHOMETER VALVE, THE PLUMBER MUST VERIFY DIMENSIONS SHOWN FOR SUPPLY ROUGHING. THIS TOILET DESIGNED TO ROUGH-IN AT A MINIMUM DIMENSION OF 254MM (10") AND A MAXIMUM DIMENSION OF 305MM (12") FROM FINISHED WALL TO C/L OF OUTLET.

FLUSHMETER VALVE REQUIREMENTS FOR 12" (305MM) ROUGH-IN: SWEAT EXTENSION NIPPLE IS REQUIRED. REFER TO VALVE MANUFACTURER AND LOCAL CODES

IMPORTANT: Dimensions of fixtures are nominal and may vary within the range of tolerances established by ANSI Standard A112.19.2. These measurements are subject to change or cancellation. No responsibility is assumed for use of superseded or voided pages.

**MADERA™ 16-1/2" HEIGHT 1.6 GPF
FLUSHOMETER TOILET SYSTEM LESS EVERCLEAN®**

- ☐ **3043.660** 1.6 gpf 16-1/2" Height Top Spud Bowl and
Selectronic® Flush Valve

BOWL:

- Floor mount elongated flushometer valve toilet
- Vitreous china
- High Efficiency. Operates in the range of 1.1 gpf to 1.6 gpf (4.2 Lpf to 6.0 Lpf)
- Conventional glaze
- 10" or 12" rough-in
- 16-1/2" rim height for accessible application
- Condensation channel
- Powerful direct-fed siphon jet action
- Fully glazed 2-1/8" trapway
- 10" x 12" water surface area
- 1-1/2" inlet spud
- 100% factory flush tested
- Less toilet seat
- Model 3043.001

SELECTRONIC® FLUSH VALVE:

- Factory-Installed CR-P2 Lithium Battery
- Self-Cleaning Piston with integral wiper spring significantly reduces clogging and maintenance
- Selectronic® Proximity System with universal sensor provides hygienic, "hands free" operation
- State-of-the-Art Electronics prevent ghost flushing
- Dezincification Resistant semi-red brass alloy
- Fully Mechanical Manual Override Button can flush the valve without power
- Fail-Safe: Valve automatically closes upon loss of power or water pressure and does not need to be reset
- Adjustable Sanitary Flush cleans the fixture & maintains the trap seal.
- Chemical Resistant EPDM Seals for extended life
- Adjustable Tailpiece for rough-in flexibility
- Can be installed left or right handed
- Model 6065.161

Includes:

- 047007-0070A Inlet Spud (furnished with bowl)
- 481310-100 2 Bolt caps with retainers (furnished with bowl)
- 1" I.P.S. angle stop with back-flow protection and vandal resistant cap
- 1" Sweat solder kit including cover tube and wall flange
- 1-1/2" High back pressure vacuum breaker, spud coupling and flange



SEE REVERSE FOR ROUGHING-IN DIMENSIONS

System MaP* Score:

- 1,000 grams of miso @ 1.6 gpf

* Maximum Performance (MaP) testing performed by IAPMO R&T Lab. MaP Report conducted by Veritec Consulting, Inc. and Koeller and Company.

Battery Life:

- 4 years @ 4,000 flushes per month

Operating Pressure:

25 psi (flowing) - 80 psi (static)

Flow Requirement:

25gpm (94.6 L/min.)

Nominal Fixture Dimensions:

718 x 356 x 419mm (28-1/4" x 14" x 16-1/2")

To Be Specified:

- ☐ Color: ☐ White

☐ Seat:


- ☐ American Standard #5901.100
Heavy duty open front less cover
- ☐ American Standard #5905.100
Extra heavy duty open front less cover

Fixture Compliance Certifications - Meets or Exceeds the Following Specifications:



- ASME A112.19.2-2008 / CSA B45.1-08 for Vitreous China Fixtures

Valve Listings:

- ASSE 1037
- ANSI/ASME A112.19.2
- ADA Compliant



*Note: The Critical Line (-C-L-) on Vacuum Breaker must typically be a minimum of 6" (152mm) above fixture. Consult Codes for details.



VALVE LEFT or RIGHT HAND INSTALLATION



MEETS THE AMERICANS WITH DISABILITIES ACT GUIDELINES
AND ANSI A117.1 REQUIREMENTS FOR ACCESSIBLE AND USABLE
BUILDING FACILITIES - CHECK LOCAL CODES.

NOTES:

TO COMPLY WITH AREA CODE GOVERNING THE HEIGHT OF VACUUM BREAKER ON THE FLUSHOMETER VALVE, THE PLUMBER MUST VERIFY DIMENSIONS SHOWN FOR SUPPLY ROUGHING. THIS TOILET DESIGNED TO ROUGH-IN AT A MINIMUM DIMENSION OF 254MM (10") AND A MAXIMUM DIMENSION OF 305MM (12") FROM FINISHED WALL TO C/L OF OUTLET.

IMPORTANT: Dimensions of fixtures are nominal and may vary within the range of tolerances established by ANSI Standard A112.19.2. These measurements are subject to change or cancellation. No responsibility is assumed for use of superseded or voided pages.



5402

Toilet Tissue Dispenser

□ Model 5402 — **Bradex**®

☑ Dual Roll

Product Materials

CABINET: 22 gauge stainless steel with exposed surfaces in architectural satin finish. Welded construction with burr-free edges.

SERVICE DOOR: 22 gauge stainless steel with exposed surfaces in architectural satin finish and tumbler lock keyed like other Bradley units. Hinged at bottom.

SPINDLES: molded polyethylene.

Capacity

Two standard core toilet tissue rolls through 5" in diameter.

Operation

Cabinet holds two rolls of 4½" x 5" standard core toilet tissue, one above the other. When first roll is used up, fresh roll automatically drops down for use. Unique retaining mechanism prevents use of spare roll until first roll is completely used. Spindles non-removable by user. Hinged door permits access to storage compartment for servicing of unit.

Installation

Verify all rough-in dimensions prior to installation. Secure to wall with mounting screws (not included) at holes provided. Mounting Kit #899-027 available from Bradley. Visit www.bradleycorp.com for more information. Provide in-wall backing at mounting screw locations.

Guide Specification

Surface-mounted dual roll toilet tissue dispenser shall be heavy gauge satin finish stainless steel and hold two standard core toilet tissue rolls.

Overall dimensions: 5½"W x 10⅜"H x 5½"D.

ADA Compliant


- ☑ Consult local and national accessibility codes for proper installation guidelines.
- ☑ Conformity and compliance to local and national codes is the responsibility of the installer.

Orders composed of products indicated as **Bradex**® will be available to ship in three days after receipt of order at the factory. There is no pricing penalty for this service from Bradley.

Page 1 of 1

1/19/2011

This information is subject to change without notice.
Bradley_TPDispenser_5402



Dim. "A" Key Surface:	For Dim. "A"	Top of Unit	Bottom of Unit
Bottom of toilet paper opening to finished floor	20" (508mm)	30¼" (768mm)	19⅞" (505mm)
	19" (483mm)	29¼" (743mm)	18⅞" (479mm)
	18" (457mm)	28¼" (718mm)	17⅞" (454mm)
	17" (432mm)	27¼" (692mm)	16⅞" (429mm)
	16" (406mm)	26¼" (667mm)	15⅞" (403mm)
	15" (381mm)	25¼" (641mm)	14⅞" (378mm)
Rough wall opening:			
Surface Mount:	No rough opening, see overall dimensions		

© 2014 Bradley
P.O. Box 309, Menomonee Falls, WI 53052-0309
800 BRADLEY (800 272 3539) +1 262 251 6000
bradleycorp.com

**Washbrook® FloWise®
Universal Urinal**

- Vitreous china
- Ultra High Efficiency, Low Consumption. Operates in the range of 0.125gpf to 1.0gpf (0.5 Lpf to 3.8 Lpf)
- Flushing rim
- Elongated 14" rim from finished wall
- Washout flush action
- Extended sides for privacy
- 3/4" inlet spud
- Outlet connection threaded 2" inside (NPTF)
- 2 wall hangers
- Fixture only
- Strainer included
- Meets ASME flush requirements at 0.125 to 1.0 gpf

- ☐ **6590.001** Universal Top spud
- ☐ **6515.001** Universal Back spud

Nominal Dimensions:

360 x 480 x 664mm
(14-1/8" x 18-7/8" x 26-1/8")

Recommended working pressure – between
20 psi at valve when flushing and 80 psi static

Compliance Certifications -

Meets or Exceeds the Following Specifications:

- ASME A112.19.2-2008/CSA B45.1-08 for Vitreous China Fixtures



SEE REVERSE FOR ROUGHING-IN DIMENSIONS

To Be Specified:

- ☐ Color: ☐ White
- ☐ Flush Valve:
 - 1.0 gpf Flush Valve: Sensor-Operated:
 - ☐ American Standard Selectronic® #6063.101.002 DC Power (Top Spud)
 - ☐ American Standard Selectronic® #6062.101.002 AC Power (Back Spud)
 - 1.0 gpf Flush Valve: Manual-Operated:
 - ☐ American Standard # 6045.101.002
 - 0.5 gpf Flush Valve: Sensor-Operated:
 - ☐ American Standard Selectronic® #6063.051.002 DC Power (Top Spud)
 - ☐ American Standard Selectronic® #6062.051.002 AC Power (Back Spud)
 - 0.5 gpf Flush Valve: Manual-Operated:
 - ☐ American Standard #6045.051.002
 - 0.125 gpf Flush Valve: Sensor-Operated:
 - ☐ American Standard Selectronic® #6063.013.002 DC Power (Top Spud)
 - ☐ American Standard Selectronic® #6062.013.002 AC Power (Back Spud)
 - 0.125 gpf Flush Valve: Manual-Operated:
 - ☐ American Standard #6045.013.002



MEETS THE AMERICANS WITH DISABILITIES ACT GUIDELINES
AND ANSI A117.1 ACCESSIBLE AND USABLE BUILDINGS AND
FACILITIES - CHECK LOCAL CODES.

- When installed so top of rim is 432mm (17") MAXIMUM from finished floor.



When used with
0.125 gpf
urinal flush valve




When used with
0.125 or 0.5 gpf
urinal flush valve




ADA
COMPLIANT

6590.001 TOP SPUD



6515.001 BACK SPUD



 MEETS THE AMERICANS WITH DISABILITIES ACT GUIDELINES
AND ANSI A117.1 ACCESSIBLE AND USABLE BUILDINGS AND
FACILITIES - CHECK LOCAL CODES.

● When installed so top of rim is 432mm (17") MAXIMUM from finished floor.

NOTES:

FLUSH VALVE NOT INCLUDED AND MUST BE ORDERED SEPARATELY.
PROVIDE SUITABLE REINFORCEMENT FOR ALL WALL SUPPORTS.

IMPORTANT: Dimensions of fixtures are nominal and may vary within
the range of tolerances established by ANSI Standard A112.19.2. These
measurements are subject to change or cancellation. No responsibility is
assumed for use of superseded or voided pages.